


TYPE A INSTALLATION
SCALE 1:10



TYPE B INSTALLATION
SCALE 1:10


TYPE 'A' INSTALLATION TO BE USED WHEN A WATERPROOF MEMBRANE IS INSTALLED. FOR TYPE 'B' INSTALLATIONS DELETE WATER BARRIER PLATE. FOR INSTALLATION AND CONNECTION DETAILS REFER DETAIL '1'

NOTES


- THIS DRAWING SHOWS TYPICAL INSTALLATION OF EARTH ELECTRODES IN CHAMBER SUBSTATIONS AND INDICATES:
 - TYPE 'A' INSTALLATION (USED ONLY WHEN A WATERPROOF MEMBRANE IS INSTALLED)
 - TYPE 'B' INSTALLATION (USED ONLY WHEN A WATERPROOF MEMBRANE IS NOT REQUIRED)
 AND SHOULD BE READ IN CONJUNCTION WITH THE SUBSTATION DRAWINGS, AND NETWORK STANDARDS NS113, NS114 AND NS116. THE TYPICAL INSTALLATION DETAILS SHOWN CAN BE USED IN EITHER A STANDARD MINIMUM EARTHING DESIGN OR A SITE SPECIFIC DESIGN.
- SUPPLY AND INSTALLATION OF EARTH ELECTRODES, FITTINGS AND CABLES IS TO BE CARRIED OUT BY THE SUBSTATION EQUIPPING CONTRACTOR BEFORE THE INSTALLATION OF ANY WATERPROOF MEMBRANE AND POURING OF THE BASEMENT OR SUBSTATION FLOOR SLAB.
- ALL TERMINATIONS AND JOINTS IN STRANDED EARTH CONDUCTORS ARE TO BE MADE BY APPROVED COMPRESSION TECHNIQUES.
- WHERE GROUND CONDITIONS PERMIT, ELECTRODES ARE TO BE DRIVEN USING APPROPRIATE ROD DRIVERS AND DRIVING HEADS. WHERE GROUND CONDITIONS REQUIRE BORE HOLES, A 35mm DIAMETER HOLE FOR ROCK OR A 50mm DIAMETER HOLE FOR CLAY IS TO BE BORED FOR EACH EARTH CABLE. AN APPROVED EARTHING COMPOUND IS TO BE PUMPED INTO THE BORE HOLE AFTER BARE EARTH CABLE HAS BEEN INSTALLED. ALL ELECTRODE AND EARTH CABLE INSTALLATIONS ARE TO BE AT THE DEPTH SPECIFIED IN THE EARTHING DESIGN.
- COPPER EARTHING CONNECTIONS ARE TO BE KEPT CLEAR OF STEEL REINFORCING OF FLOOR SLAB WHERE POSSIBLE. OTHERWISE INSULATED CABLES ARE TO BE USED AND COMPRESSION FITTINGS ARE TO BE TAPED OVER.
- A SUITABLE GALVANISED STEEL DRAW-IN BOX IS TO BE INSTALLED AT EACH CHANGE OF DIRECTION. THE BOX IS TO BE MOUNTED SUCH THAT IT IS ACCESSIBLE TO AUSGRID STAFF AT ALL TIMES. IF A CABLE JOIN IS REQUIRED INSIDE THE BOX, ENSURE THE BOX IS LARGE ENOUGH TO HOUSE CRIMPING JOINTS SHOWN IN DETAIL '2'. WHERE A VERTICAL CABLE JOIN IS REQUIRED WITHIN A DRAW-IN BOX THE BOTTOM CABLE IS TO BE PROPERLY SUPPORTED WITH SADDLE OR CABLE TIE SO THAT NO STRESS IS PLACED ON THE CONNECTING CRIMPS.
- THE MECHANICAL PROTECTION TO CABLES AND CRIMPED JOINTS SHOWN IN LOW BASEMENT INSTALLATIONS IS TO BE PERFORMED BY A REMOVABLE GALVANISED STEEL COVER. THIS COVER IS TO BE ACCESSIBLE TO AUSGRID STAFF AT ALL TIMES.
- THE INSTALLATION AND CONNECTION OF THE EARTH RODS AND CONNECTING CABLES ARE TO BE INSPECTED AND APPROVED BY AUSGRID'S NOMINATED OFFICER BEFORE THE INSTALLATION OF ANY WATERPROOF MEMBRANE AND POURING OF THE BASEMENT OR SUBSTATION FLOOR SLAB. CONNECTING CABLES FOR EACH EARTHING GROUP UNDER THE SLAB MUST BE CONTINUOUS AND CONNECTIONS TO ELECTRODES OR BARE WIRE FOR BORE HOLES AS DETAILED.
- ALL 70mm² EARTH CABLEING TO BE BLACK INSULATED STRANDED COPPER CONDUCTOR.
- CABLES ARE TO BE PROPERLY SUPPORTED WITH SADDLES TO THE WALL OR CABLE TIES SO THAT NO STRESS IS PLACED ON THE LUG CONNECTION TO EARTH BAR.

TYPES A & B INSTALLATIONS CONSTRUCTED WITH TOPPING SLAB


SCALE 1:10




TYPES A & B INSTALLATIONS WITH EARTH RODS IN THE LOWEST BASEMENT LEVEL
SCALE 1:10




DETAIL 1 WATER BARRIER PLATE INSTALLATION
SCALE 1:2




CONNECTIONS FOR BORE HOLE CABLE TYPE ELECTRODE
SCALE 1:5



DETAIL 2 CONNECTING EARTH CABLES
SCALE 1:5



PREFERRED



ALTERNATIVE

CONNECTIONS FOR DRIVEN ROD TYPE EARTH ELECTRODES
SCALE 1:5

IF THE CHAMBER SUBSTATION SITE DOES NOT MEET THE CRITERIA FOR STANDARD MINIMUM EARTHING, A SITE SPECIFIC EARTHING DESIGN MUST BE UNDERTAKEN

CAD DRAWING DO NOT MANUALLY AMEND AMENDMENTS 12. SHOW VARIOUS TYPES OF INSTALLATIONS. P.JARVIS 11/12/1990 DTC CHECKED: DGH APPROVED: 13. REF E2, C10. DRAW-IN BOX AND NOTES 6 AND 7 ADDED. P.JARVIS 01/11/1991 BJT CHECKED: DGH APPROVED: 14. EARTH ROD SPACING AND NOTES ALTERED TO NETWORK STANDARDS. P.JARVIS 02/05/2001 MPEACK CHECKED: MPEACK APPROVED: 99/11/07/5 PN: 15. NOTES 1 AND 4 ALTERED TITLE CHANGED FROM SUBSTATION EARTHING TYPICAL INSTALLATION OF EARTH ELECTRODES. MP 18/01/2005 IMR CHECKED: PWJ APPROVED: ES103/59/1/2 PN: 16. DETAILS & REFERENCES TO TUBE TYPE COMPRESSION FITTINGS REPLACED BY C AND P TYPE COMPRESSION FITTINGS. NOTE 4 UPDATED. PWJ 04/09/2006 IMR CHECKED: IMR APPROVED: ES103/59/1/2 PN: 17. NEW DRAWING BORDER ADDED. TUBE TYPE EARTH ELECTRODES REMOVED. ROD TYPE ELECTRODES DETAIL AMENDED. CMABBUTT 10/01/2012 P.JARVIS CHECKED: MOKELLY APPROVED: PH02-02010-1-4-1 PN: 18. DETAIL FOR BORE HOLE EARTHING ADDED. DETAIL '2' ADDED. DETAIL '1', TYPE 'A' & TYPE 'B' AMENDED TO SHOW NEW CABLE CONNECTION METHOD. TO COPPER TUBING. NOTES 1, 4, 6 & 8 AMENDED. NOTES 9 & 10 ADDED. CMABBUTT 14/03/2012 P.JARVIS CHECKED: MOKELLY APPROVED: PH02-02010-1-4-1 PN: 19. NOTE 1 AND EARTHING DESIGN NOTE ALTERED TO REFLECT CRITERIA FOR STANDARD MINIMUM EARTHING DESIGN. P.JARVIS 24/06/2016 B.STADDON/M.CHARAN CHECKED: D.GREY APPROVED: OPEX 6568-1-1-6 PN: 20. NOTE AMENDED ON DETAIL 1. P.RIOS 04/11/2021 C.MABBUTT CHECKED: P.TURRIN APPROVED: 21. EARTHBAR SPACER CHANGED FROM 40mm TO 60mm. P.RIOS 11/01/2024 P.TURRIN CHECKED: G.FORD APPROVED: 22. BORDER & TITLE BLOCK UPDATED. M.BENNETT 08/09/2024 L.MARTINUTZI CHECKED: M.BENNETT APPROVED:	SCALE AS SHOWN DESIGNED - DRAWN J.BROOKER CHECKED IGH APPROVED JP DATE 30/11/1961 TRIM REF - PROJECT NUMBER 18745	CHAMBER SUBSTATION EARTHING TYPICAL INSTALLATION OF EARTH ELECTRODES DRAWING No 25121 SHEET 1 AMD 22 SIZE A1
	ISSUED FOR CONSTRUCTION	DRAWING No 25121 SHEET 1 AMD 22 SIZE A1