



NS 171 DETAIL - APPENDIX B



PLAN VIEW



NOTES:

1. CABLES IN TRENCHES ADJACENT OIL FILLED EQUIPMENT ARE TO BE COATED WITH AN APPROVED CABLE COATING AS DETAILED ABOVE WHEN THE TRENCH IS LOCATED WITHIN THE 2:1 SPLASH ZONE.
2. THE CABLES ONLY ARE TO BE COATED NOT THE INSIDE OF THE TRENCH TO FACILITATE DRAINAGE.
3. LENGTH OF CABLE TO BE COATED IS TO BE FREE OF ORGANIC MATERIAL & DUST.
4. WHERE CABLES ENTER A BUILDING VIA A CABLE TRENCH, THE CABLE SHOULD BE COATED FOR A DISTANCE OF 1.5m FROM THE BUILDING.
5. CABLE COATING IS TO BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS INSTRUCTIONS.
6. REFER TO A4-128464 FOR APPLICATION LIMITATIONS.

LIMITATIONS OF USE:

- i. ONLY TO BE USED WHERE CABLES IN TRENCH ADJACENT OIL FILLED EQUIPMENT.

CAD DRAWING DO NOT MANUALLY AMEND AMENDMENTS
1. DRY FILM THICKNESS ADDED. RMI 30.09.2002
2. PLAN AND SECTION REVISED. JA 07.01.04
3. NEW AUSGRID BORDER & LOGO ADDED. PLAALAA 23-10-2013 APPROVED T.LAMPARD



SCALE	1:20
DESIGNED	
DRAWN	CJS
CHECKED	JW
APPROVED	M-DESIGN JW
DATE	18/07/2002

CABLE TRENCH COATING
NEAR OIL FILLED EQUIPMENT IN
EXTERNAL YARDS.

PROJECT No.	ES 102-9-1
PRJTRK No.	
Sheet	1
A4	128123
	3